

## 西町八軒町1号線 当初設計

[illegible]

		D切断		P切断		P切断		P切断		P切断		P切断		P切断		P切断		P切断		D切断			
		○1-(1)		○1-(2)		○1-(3)		○1-(4)		○2-(1)													
既設管接続	番 号	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	数量						
	記号入力			h5012				h5012		h5012		h5012		h5012	mpp50								
	口径	75×50	50	50	50	50	50	50	50	50	50	50	50	50	50								
	管種	サドル分水栓	分止水栓ソケット	乙切管	分止水栓ソケット	青銅弁	分止水栓ソケット	乙切管	EFエルブ	乙切管	EFエルブ	乙切管	EFエルブ	乙切管	分製シロイタ P×G								
	数量																0						
	管布設	0		2.5				1.0	0	1.0	0	0.40	0	2.0	0.0		6.9						
	区間	0		2.5				1.0	0	1.0	0	0.00	0	2.0	0.0		6.5						
	1口継手																0						
	2口継手								1		1		1				3						
	P継手		1		1		1										3						
	ねじ込み		1		1		1										3						
	管切断			1				1		1				1	1		6						
	フランジ継手																0						
	メカ接合														2.00		2						
	土工①																0.0						
土工②			0.000		0.000		0.000		0.000		0.000		0.000		2.000	0.000		6.5					

分水Φ13  11件	番 号	1	2	3	4	5	6	1件当たり	数量
	記号入力			pep13	pL13	ws13			
	口径	75×20	20×13	13	13	13	13		
	管種	サドル分水栓	PE直轄ソケット	PEP管	PRongエルボ	W止水栓	テータックス		
	数量							0.000	0.000
	管布設			3.0				3.0	33.0
	区間			3.0				3.0	33.0
	ポリ継手		1		1			2	22
	管切断			1				1	11
	管ねじ切り							0	0
ねじ込接合		1					1	11	
F接合							0	0	
土工③			3.0				3.0	33.0	
P切断									

分水Φ20  1件	番 号	1	2	3	4	5	6	1件当たり	数量
	記号入力	1441002	petks20	pep13	pL13	ws13			
	口径	75×20	20	20	20	20	20		
	管種	サドル分水栓	PE直結ソケット	PEP管	Pロングエルボ	W止水栓	メータボックス		
	数量							0.000	0.000
	管布設			3.0				3.0	3.0
	区間			3.0				3.0	3.0
	ボリ継手		1		1			2	2
	管切断			1				1	1
	管ねじ切り ねじ込接合		1					0	0
F接合							1	1	
							0	0	
土工③			3.0				3.0	3.0	
P切断									

## 集計表

	管種	管径	管路工①	既設管接 続	分土工①	分土工②		合計
布設延長	HPPE(m)	100						0.0
		75	89.2					89.2
		50		6.9				6.9
	PEP(m)	25						0.0
		20						0.0
		13				0.0		0.0
	計		89.2	6.9	0.0	0.0	0.0	96.1
区間延長	HPPE(m)	100						0.0
		75	89.7					89.7
		50		6.5				6.5
	PEP(m)	25						0.0
		20						0.0
		13				0.0		0.0
	計		89.7	6.5	0.0	0.0		96.2
直管本 数	HPPE(本)	100						0
		75	18.0					18.0
		50		2.0				2

## 切管調書

[illegible]

番号 Φ50	長さ						切管計	残管	計
	ブレーン管	(1)	(2)	(3)	(4)	(5)			
1 (HPPE)		2.5 ▼	1.0 ▼	1.0 ▼	0.4 ▼		4.9	0.1	5.0
2 (HPPE)		2.0 ▼					2.0	3.0	5.0

土工集計

	管路工①	既設管接続	分水	合計
土工①	90.2			90.2
土工②	0.0	6.5		6.5
給水土工			36.0	36.0

## 西町八軒町1号線(仮設) 当初設計

仮設工

分水Φ13 11件

分水Φ20 1件